

**TRANQUILITY ESTATES
WATER DISTRIBUTION SYSTEM
WATER MAIN UPGRADE
RAYMOND, NEW HAMPSHIRE**

ADDENDUM #2

DATE: August 12, 2024
TO: PLAN HOLDERS

This ADDENDUM #2 shall become part of the Bidding Documents and Contract Documents for the above referenced project. BIDDERS, please acknowledge receipt of this ADDENDUM #2 on the BID FORM (Page 1). This ADDENDUM #2 consists of 1 page in total that stems from the Pre-Bid Walkthrough on August 6, 2024.

1. As noted in sheet C1.1 on the plan set, the intent of this project is to directionally bore the new watermain to the maximum extent possible.
 - a. Any permits that are required from deviating construction methods will be the responsibility of the selected contractor to obtain.
2. Soil explorations were advanced on-site in November 2023. No soil classification was conducted. No refusal was observed within the 0-8' bgs range. No groundwater was observed within the 0-8' bgs range.
3. Old watermain can be left in place after construction; however, valve boxes must be removed.
4. This project does not have AIS or Davis-Bacon requirements.
5. As shown on the plan sets, the intent of the project is to bring new service connections to existing curb stops; and then replace the curb stops.
6. As shown on the plan set, new service connections are to be $\frac{3}{4}$ ".
7. Site prep (tree removal, yard features removal, etc.) will be coordinated with the resident project representative (RPR), the selected contractor, and community representatives.
 - a. Pre-construction Photos are required as per specifications.
8. Staging at the site can be completed in the field adjacent to the south/southeast of the maintenance/pump house. However, items are to remain outside of the nearby well radius of 200 feet as required by NHDES Env-Dw 305.10.
9. As-Builts – please refer to Section 01 77 19 of the project bid specifications document.

End of Addendum #2